

DETAILED TENDER DOCUMENT.

NAME OF WORK :: CONSTRUCTION OF TEMPORARY SHEDS FOR WATCH & WARD DUTY FOR STORAGE SITE OF PORCUPINE BARS, 1(ONE) NUMBER EACH AT (A) TEKELIPHUTA, (B) PADUMANI & (C) KARATIPAR, MAJULI.

NIT No. :: BB/LD/T-89/2010/ dated....

Group No. :: 3

Location :: (A)Tekeliphuta, Majuli.
(B)Upper Padumani, Majuli
(C)Karatipar. Majuli.

Issued to ::

Issued by ::

EXECUTIVE ENGINEER.
LAKHIMPUR DIVISION
BRAHMAPUTRA BOARD
NORTH LAKHIMPUR.

DETAILED TENDER DOCUMENT.

NAME OF WORK :: CONSTRUCTION OF TEMPORARY SHED ALONG WITH PIT
LATRINE AND HAND TUBE WELL NEAR BOULDER SPUR No. 4 AT
MAJULI.

NIT No. :: BB/LD/T-89/2010/ dated....

Group No. :: 1

Location :: Near boulder Spur No. 4, Afalamukh, Majuli.

Issued to ::

Issued by ::

EXECUTIVE ENGINEER.
LAKHIMPUR DIVISION
BRAHMAPUTRA BOARD
NORTH LAKHIMPUR.

DETAILED TENDER DOCUMENT.

NAME OF WORK :: CONSTRUCTION OF TEMPORARY SHED ALONG WITH PIT
LATRINE AND HAND TUBE WELL NEAR BOULDER SPUR No. 8 AT
MAJULI.

NIT No. :: BB/LD/T-89/2010/ dated....

Group No. :: 2

Location :: Near boulder Spur No. 8, Sumoimari, Majuli.

Issued to ::

Issued by ::

EXECUTIVE ENGINEER.
LAKHIMPUR DIVISION
BRAHMAPUTRA BOARD
NORTH LAKHIMPUR.

GOVERNMENT OF INDIA
(MINISTRY OF WATER RESOURCES)
OFFICE OF THE EXECUTIVE ENGINEER:LAKHIMPUR DIVISION,
BRAHMAPUTRA BOARD:NORTH LAKHIMPUR

NO.: BB/LD/T-89/2010/

dated....

NOTICE INVITING TENDER

Sealed tenders in prescribed format, on behalf of the Brahmaputra Board, are hereby invited by the Executive Engineer, Lakhimpur Division, Brahmaputra Board, North Lakhimpur from the approved and eligible contractors of Central Govt./ State Govt. Departments for the works as detailed below. –

Gr. No	Name of Work	Location of Work	Estimated value (Rs.)	Earnest Money Deposit (Rs.)	Cost of tender paper - I.P.O (Rs.)	Time of completion
1	2	3	4	5	6	7
1	Construction of Temporary Shed along with Pit Latrine and Hand Tube Well near the Boulder Spur No. 4 at Majuli.	Near boulder Spur No. 4, Afalamukh, Majuli.	90,185.00	2255.00	150.00	10 days
2	Construction of Temporary Shed along with Pit Latrine and Hand Tube Well near the Boulder Spur No. 8 at Majuli.	Near boulder Spur No. 8, Sumoimari, Majuli.	90,185.00	2255.00	150.00	10 days
3	Construction of Temporary Sheds for watch & ward duty for storage site of porcupine bars, 1(one) number each at (A) Tekeliphuta, (B) Padumani & (C) Karatipar, Majuli.	(A)Tekeliphuta, Majuli. (B)Upper Padumani, Majuli (C)Karatipar. Majuli.	3 x 11812.00 = 35,436.00	886.00	150.00	10 days

Detailed tender papers, terms and condition, etc. may be had from the office of the undersigned on any working day between 11.00 hours and 15.00 hours w.e.f. 5.8.11 to 12.8.11 on all working days on a written request enclosing attested copies of Registration certificate, up to date Income Tax Clearance Certificate / PAN card, VAT Registration Certificate / VAT Clearance Certificate and non refundable crossed **I.P.O.** of the value as per column no. 5 of the NIT, drawn in favour of the **Financial Adviser, Brahmaputra Board, Basistha, Guwahati -29.** The tenderer shall have to submit **Earnest Money Deposit** as mentioned above in the form of FDR/DD/Deposit at call receipt drawn from any scheduled Bank guaranteed by Reserve Bank of India payable at **North Lakhimpur in favour of the Executive Engineer, Lakhimpur Division, Brahmaputra Board, North Lakhimpur.** The sealed tenders, along with all the documents stated above, will be received in the office of the undersigned up to 15.00 hours of 16.8.11 and will be opened on the same day at 15.30 hours in presence of tenderers /his representatives, if any. The tenders not accompanied with the aforesaid documents are liable to be rejected. Brahmaputra Board follows the CPWD procedures and so the bidders are advised to get themselves acquainted with the CPWD manual/ procedures and CPWD Form – 8.

Details of tender can also be seen at Brahmaputra Board's web site www.brahmaputraboard.gov.in/www.tender.gov.in and the office Notice Board. The bidders may download the tender directly from above web site. However, the bidders will have to deposit the cost of tender papers in the same manner with the tender documents.

The undersigned reserves the right to accept or reject any or all of the tenders without assigning any reason thereof.

Executive Engineer

Copy to :

1. The Chief Engineer (I&W), Brhamaputra Board, Basistha, Guwahati – 29 for favour of kind information.
2. The Superintending Engineer, Tinsukia Circle, Brahmaputra Board, Tinsukia for favour of kind information.
3. The In-Charge, I.T. Cell, Brahmaputra Board, Guwahati – 29 for information and necessary action.
4. Sri P.K. Khatoniyar, Assistant Executive Engineer (W&B), Brhamaputra Board, Basistha, Guwahati – 29 for information and necessary action.
5. The Assistant Executive Engineer, Majuli Sub Division – I, Brahmaputra Board, Majuli / Lakhimpur Sub-Division, Brahmaputra Board, North Lakhimpur for information and wide circulation.
6. The Divisional Accountant, Lakhimpur Division, Brahmaputra Board, North Lakhimpur.
7. Notice Board.
8. Relevant file.

Executive Engineer

TERMS AND CONDITION.

1. Rate should be quoted both in figure and words. Any correction or alteration should be properly initialed. Over writing in any case is liable for rejection. In case of difference in rate quoted in words and figures, the rate in words will be taken into account.
2. Earnest Money Deposit as applicable, should be submitted in the form of FDR/DD/Deposit at Call receipt drawn from any scheduled bank guaranteed by Reserve Bank of India payable at North Lakhimpur in favour of the Executive Engineer, Lakhimpur Division, Brahmaputra Board, North Lakhimpur.
3. Tender Agreement is to be executed in CPWD form No.8 and agreed upon along with all additions and omissions.
4. CPWD norms will be followed.
5. Detailed Tender document will be issued on a written request enclosing attested copies of Registration Certificate, up to date Income Tax Clearance Certificate / PAN, VAT Registration Certificate / VAT Clearance Certificate and non refundable crossed **I.P.O.** of the value as per column no. 6 of the NIT, drawn in favour of the **Financial Adviser, Brahmaputra Board, Basistha, Guwahati -29**
6. Name and address of the tenderer, NIT No. and Group No. of the tender should be marked on the sealed envelop while submitting the tender.
7. The undersigned reserves the right to accept or reject any or all of the tenders without assigning any reason thereof and does not bind himself to accept the lowest rate.
8. Decision of the tender committee will be final and binding on the tenderers.

Executive Engineer.

NAME OF WORK :: CONSTRUCTION OF TEMPORARY SHED ALONG WITH PIT LATRINE AND HAND TUBE WELL NEAR BOULDER SPUR No. 4 AT MAJULI.

NIT No. :: BB/LD/T-89/2010/ dated....

Group No. :: 1

Location :: Near boulder Spur No. 4, Afalamukh, Majuli.

Item No.	Item of Work:	Unit	Estimated Quantity	Rate in figure (Rs.)	Rate in word (Rupees.)	Amount (Rs)
1	2	3	4	5	6	7
1	Surface dressing of ground including removing vegetation/or undulation of ground not exceeding 150mm deep and disposal of rubbish out side the periphery and lift up to 1800mm in all kind of soil.	Sqm.	400	Rs. Rupees	Rupees Rs	Rs
2	Construction of Temporary shed with 300mm high plinth and floor, Bhuluka bamboo post driving at least 750mm under ground, height above plinth 2400mm, wattle wall mud plastered and white wash 2(two) coats, 100mm thick thatched roof, double mat doors and windows etc. complete as directed and specified. (c)With whole Jati bamboo Kami frame	Sqm.	111.63	Rs. Rupees	Rupees Rs	Rs
3	Construction of pit latrine of pit size 1.00m dia. and 2.5m depth, 65mm thick c.c flooring with one flat brick soling, covered by brick wall up to plinth filling with white vitreous china water closet squatting pan and S/P trap, one no. of bitumen drum, 100mm dia. PVC pipe connecting to the pit with necessary earth work in excavation for the pit and earth/sand filling in the plinth and steps etc. including bamboo split wall and wooden frame door complete as directed. (Considering 1 unit)	No.	1	Rs. Rupees	Rupees Rs	Rs
4	Supplying and installation of a hand tube well including 26.05Rm 40mmdia. G.I pipe boring and providing of bentonite clay packing around G.I pipe including one number 40mm dia strainer with hand pump along with cement concrete platform of 1:2:4 mix of 1.50m dia., and 0.15m thick cement concrete drain in proportion 1:2:4 mix of length 3m complete as directed.	No.	1	Rs. Rupees	Rupees Rs	Rs

Signature of Contractor.

Executive Engineer.

NAME OF WORK :: CONSTRUCTION OF TEMPORARY SHED ALONG WITH PIT LATRINE AND HAND TUBE WELL NEAR BOULDER SPUR No. 8 AT MAJULI.

NIT No. :: BB/LD/T-89/2010/ dated....

Group No. :: 2

Location :: Near boulder Spur No. 8, Sumoimari, Majuli.

Item No.	Item of Work:	Unit	Estimated Quantity	Rate in figure (Rs.)	Rate in word (Rupees.)	Amount (Rs)
1	2	3	4	5	6	7
1	Surface dressing of ground including removing vegetation/or undulation of ground not exceeding 150mm deep and disposal of rubbish out side the periphery and lift up to 1800mm in all kind of soil.	Sqm.	400	Rs. Rupees	Rupees Rs	Rs
2	Construction of temporary shed with 300mm high plinth and floor, bhuluka bamboo post driving at least 750mm under ground, height above plinth 2400mm, wattle wall mud plastered and white wash 2(two) coats, 100mm thick thatched roof, double mat doors and windows, etc. complete as directed and specified. (c)With whole Jati bamboo Kami frame	Sqm.	111.63	Rs. Rupees	Rupees Rs	Rs
3	Construction of pit latrine of pit size 1.00m dia. and 2.50m depth, 65mm thick c.c flooring with one flat brick soling, covered by brick wall up to plinth filling with white vitreous china water closet squatting pan and S/P trap, one no. of bitumen drum, 100mm dia. PVC pipe connecting to the pit with necessary earth work in excavation for the pit and earth/sand filling in the plinth and steps etc. including bamboo split wall and wooden frame door complete as directed. (Considering 1 unit)	No.	1	Rs. Rupees	Rupees Rs	Rs
4	Supplying and installation of a hand tube well including 26.05Rm 40mmdia. G.I pipe boring and providing of bentonite clay packing around G.I pipe including one number 40mm dia strainer with hand pump along with cement concrete platform of 1:2:4 mix of 1.50m dia., and 0.15m thick cement concrete drain in proportion 1:2:4 mix of length 3m complete as directed.	No.	1	Rs. Rupees	Rupees Rs	Rs

Signature of Contractor.

Executive Engineer.

NAME OF WORK :: CONSTRUCTION OF TEMPORARY SHEDS FOR WATCH & WARD DUTY FOR STORAGE SITE OF PORCUPINE BARS, 1(ONE) NUMBER EACH AT (A) TEKELIPHUTA, (B) PADUMANI & (C) KARATIPAR, MAJULI.

NIT No. :: BB/LD/T-89/2010/ dated....
 Group No. :: 3
 Location :: (A)Tekeliphuta, Majuli.
 (B)Upper Padumani, Majuli
 (C)Karatipar. Majuli.

Item No.	Item of Work:	Unit	Estimated Quantity	Rate in figure (Rs.)	Rate in word (Rupees.)	Amount (Rs.)
1	2	3	4	5	6	7
1	Construction of temporary shed with 300mm high plinth and floor, bhuluka bamboo post driven at least 750mm under ground, height above plinth 2400mm, wattle wall mud plastered and white wash 2(two) coats, 100mm thick thatched roof, double mat doors and windows etc. complete as directed and specified. (a) With whole Jati Bamboo rua frame, (A) at Tekeliphuta, Majuli.	Sqm.	16.80	Rs. Rupees	Rs. Rupees	Rs.
2	Construction of temporary shed with 300mm high plinth and floor, bhuluka bamboo post driven at least 750mm under ground, height above plinth 2400mm, wattle wall mud plastered and white wash 2(two) coats, 100mm thick thatched roof, double mat doors and windows etc. complete as directed and specified. (a) With whole Jati Bamboo rua frame, (B) at Upper Padumoni, Majuli.	Sqm.	16.80	Rs. Rupees	Rs. Rupees	Rs.
3	Construction of temporary shed with 300mm high plinth and floor, bhuluka bamboo post driven at least 750mm under ground, height above plinth 2400mm, wattle wall mud plastered and white wash 2(two) coats, 100mm thick thatched roof, double mat doors and windows etc. complete as directed and specified. (a) With whole Jati Bamboo rua frame, (C) at Karatipar, Majuli.	Sqm.	16.80	Rs. Rupees	Rs. Rupees	Rs.

Signature of Contractor

Executive Engineer.

